



NOTES:

1. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED
2. IT IS THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN LOCATES OF ALL EXISTING UTILITIES AND SERVICING PRIOR TO INSTALLATION
3. DO NOT DAMAGE VISIBLE TREE ROOTS WHEN INSTALLING T-BARS
4. GEOTEXTILE TO BE WOVEN OR NON-WOVEN. MINIMUM EQUIVALENT OPENING SIZE 0.15mm MAXIMUM EQUIVALENT OPENING SIZE 0.25mm
5. GEOTEXTILE TO HAVE HORIZONTAL OVERLAP OF 1000mm MINIMUM AT JOINTS
6. SEDIMENT CONTROL FENCE MUST BE MAINTAINED IN SOUND CONDITION THROUGH ALL PHASES OF CONSTRUCTION UNTIL APPROVAL TO REMOVE
7. SEDIMENT CONTROL FENCE TO BE REMOVED AT CONSTRUCTION COMPLETION UPON APPROVAL BY TOWN STAFF
8. SEDIMENT FENCING SHALL BE INSTALLED IN ACCORDANCE WITH LOCATIONS INDICATED IN AN APPROVED CONSTRUCTION / TREE INVENTORY & PRESERVATION PLAN TO ONTARIO PROVINCIAL STANDARDS (OPSD - 219.110 / OPSD - 219.131) AND TO THE TOWNS SATISFACTION

THE CORPORATION OF THE TOWN OF WHITBY **PLANNING & DEVELOPMENT DEPARTMENT**

CHECKED	<i>[Signature]</i>
APPROVED	<i>[Signature]</i>
SCALE:	N.T.S

SEDIMENT CONTROL FENCE

DWG. DATE:	JANUARY 2021
REVISION No.:	001
REVISION DATE:	
DWG No.	732