BUFFER PLANTING NOTES

- LAYOUT OF FINAL BUFFER PLANTING LOCATIONS WILL BE COMPLETED IN ACCORDANCE WITH THE REQUIREMENTS OF THE SUBDIVISION PLANTING INSPECTION NOTES STANDARD DETAIL 752.
- 1. PLANT MATERIAL WILL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING MINIMUM SETBACKS FROM ADJACENT SIDEWALKS, MULTI-USE PATHS AND TRAILS:
 - 2.0 M FOR DECIDUOUS TREES
 - 3.0 M FOR CONIFEROUS TREES
 - 1.5 M FOR SHRUBS
- 3. A MINIMUM 2.0 M WIDE MOWING STRIP WILL BE PROVIDED WHEREVER POSSIBLE ADJACENT TO WALKWAYS PROVIDED THROUGH OPEN SPACE AREAS.

GENERAL SIDEWALK, MULTI-USE PATH AND TRAIL NOTES

- 1. ALL CONCRETE SIDEWALKS WILL BE;
 - CONSTRUCTED AS PER TOWN OF WHITBY DESIGN CRITERIA AND ENGINEERING STANDARDS AND STANDARD DETAIL 208;
 - CONSTRUCTED WITH MINIMUM SLOPES TO ENSURE ACCESSIBILITY;
 - · A MINIMUM WIDTH OF 1500 MM UNLESS OTHERWISE REQUIRED; AND
 - LABELLED AS "CASH-IN-LIEU OF 1.5 M CONCRETE SIDEWALK" WHERE APPROPRIATE IN COMPLIANCE WITH THE REQUIREMENTS OF THE ASSOCIATED SUBDIVISION AGREEMENT.
- 2. ASPHALT MULTI-USE PATHWAYS WILL BE CONSTRUCTED AS PER TOWN OF WHITBY DESIGN CRITERIA AND ENGINEERING STANDARDS AND STANDARD DETAIL 214.0.
- 3. ALL TRAILS WILL BE CONSTRUCTED;
 - WITH A MAXIMUM LONGITUDINAL SLOPE OF 5% AND MAXIMUM CROSS SLOPE OF 2%; AND
 - WITH A MINIMUM 1.5 METRE SOD MOWING/MAINTENANCE SHOULDER ON BOTH SIDES OF THE TRAIL, SLOPED AT A MAXIMUM OF 25%.
 - · WITH AN ALIGNMENT THAT PROVIDES A MINIMUM 1.5 METRE SETBACK FROM RESIDENTIAL PROPERTY

THE CORPORATION OF THE TOWN OF WHITBY

PLANNING & DEVELOPMENT DEPARTMENT

APPROVED SCALE: N.T.S