



- NOTES:
1. ALL DIMENSIONS IN MILLIMETERS UNLESS OTHERWISE NOTED
  2. AT TIME OF PLANTING, CONTRACTOR WILL BE RESPONSIBLE FOR INSTALLING WATER BAG ON EACH DECIDUOUS TREE PLANTED. THE WATER BAG SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER’S INSTRUCTIONS
  3. PRIOR TO FINAL INSPECTION, THE CONTRACTOR SHALL REMOVE THE WATER BAG
  4. ENSURE ALL TAGS, ROPES, STRAPS, TREE WRAPS AND CONTAINERS ARE REMOVED FROM TREE
  5. REFER TO STANDARD #755 – 755.20 FOR PLANT MATERIAL SPECIFICATIONS
  6. REFER TO STANDARD #753: TOPSOIL NOTES FOR PLANTING SOIL REQUIREMENTS
  7. REFER TO TREE PIT STANDARD #514 FOR STREET TREE INSTALLATIONS

<b>THE CORPORATION OF THE TOWN OF WHITBY</b>		<b>PLANNING &amp; DEVELOPMENT DEPARTMENT</b>	
CHECKED <i>[Signature]</i>	<b>DECIDUOUS TREE PLANTING WITH 75 L WATER BAG</b>	DWG. DATE: <b>JANUARY 2021</b>	
APPROVED <i>[Signature]</i>		REVISION No.: <b>002</b>	
SCALE: <b>N.T.S</b>		REVISION DATE: <b>MAY, 2022</b>	DWG No. <b>715</b>