

NOTES:

- 1. ALL DIMENSIONS IN MILLIMETERS UNLESS OTHERWISE NOTED
- 2. REMOVE ANY WRAPPINGS OR RUBBER BANDS BEFORE INSTALLING APPROVED MATERIAL.
- 3. REFER TO STORMWATER MANAGEMENT POND LANDSCAPE PLAN FOR LOCATIONS AND QUANTITIES OF PLANTINGS

PLANTING NOTES:

- 1. SMALL CLUMPS CONTAINING ONE OR TWO LEAFY STEMS AND HEALTHY ROOTSTOCKS AND RHIZOMES (I.E UNDERGROUND STEMS) SHOULD BE TRANSPLANTED TO JUST BELOW THE PERMANENT WATER LEVEL (I.E IN WATER NO GREATER THAN 0.3m DEEP FOR EMERGENTS AND NO LESS THAN 0.3m
- 2. NO GREATER THAN 1.0m DEEP FOR SUBMERGENTS
- 3. ROOTS SHOULD BE PLANTED IN THE BOTTOM SUBSTRATE TO A DEPTH OF APPROXIMATELY 10cm, WITH INDIVIDUAL CLUMPS DISTRIBUTED ALONG THE SHORELINE EVERY 0.75 1.5 METERS. AQUATICS SHALL PREFERABLY BE PLANTED DURING DORMANCY (I.E FALL MID TO LATE OCTOBER), EARLY SPRING (APRIL) AS AN ALTERNATIVE
- 4. PLANTING SHALL BE PROVIDED IN ACCORDANCE WITH THE STANDARDS OF THE M.O.E STORMWATER MANAGEMENT PLANNING AND DESIGN MANUAL AND RECOMMENDED PLANT SPECIES
- 5. TOPSOIL SHALL BE PROVIDED IN ACCORDANCE WITH STANDARD #753: TOPSOIL NOTES
- 6. IN SHALLOW WATER ZONES, PLANTING ROWS SHALL BE PERPENDICULAR TO THE DIRECTION OF WATER FLOW TO MINIMIZE POTENTIAL CHANNELIZATION

THE CORPORATION OF THE TOWN OF WHITBY

PLANNING & DEVELOPMENT DEPARTMENT

CHECKED	lub:	
APPROVED	×	
SCALE:	N.T.S	

STORMWATER MANAGEMENT POND FRINGE AND AQUATIC PLANTINGS

DWG. DATE: JANUARY 2021	
REVISION No.: 002	
REVISION DATE: MAY. 2022	
DWG No. 720	